



CLOSED-CIRCUIT TELEVISION

Intelligent Transport Systems (ITS) Design Standard

22 MAY 2023
VERSION 1.0

Copyright information

Copyright ©. This copyright work is licensed under the Creative Commons Attribution 4.0 International licence. You are free to copy, distribute and adapt the work if you attribute the work to the Waka Kotahi NZ Transport Agency (Waka Kotahi) and abide by the other licence terms. To view a copy of this licence, visit <http://creativecommons.org/licenses/by/4.0/>

Disclaimer

Waka Kotahi has endeavoured to ensure material in this document is technically accurate and reflects legal requirements. However, the document does not override governing legislation.

Waka Kotahi does not accept liability for any consequences arising from the use of this document. If the user of this document is unsure whether the material is correct, they should refer directly to the relevant legislation and contact Waka Kotahi.

More information

If you have further queries, contact the Intelligent Transport Systems Standards and Specifications (ITS S&S) team via email: itsspec@nzta.govt.nz

More information about ITS is available on the Waka Kotahi website at <https://www.nzta.govt.nz/its>

This document is available on the Waka Kotahi website at <https://www.nzta.govt.nz/itsspecs>

Template version

1.21, 03/11/2021

Contents

1	DOCUMENT CONTROL	6
1.1	Document information	6
1.2	Document owner	6
1.3	Document approvers	6
1.4	Version history – major changes	7
2	TERMINOLOGY USED IN THIS DOCUMENT	8
3	OVERVIEW AND OUTCOMES	9
3.1	Purpose	9
3.2	Overview	9
3.2.1	Definition	9
3.2.2	Waka Kotahi ITS class	9
3.3	Scope	10
3.4	Outcomes	10
3.4.1	Operational	11
3.4.2	For users of the transport network	11
3.4.3	For road controlling authorities and transport operations centres	11
4	DESIGN FOR OPERATION	12
4.1	Operational visibility	12
4.2	Site selection	12
4.2.1	End-user requirements	12
4.2.2	Privacy	13
4.2.3	Environmental	13
4.2.3.1	Infrastructure geometry	13
4.2.3.2	Trees and foliage	14
4.2.3.3	Physical structures	14
4.2.3.4	Vehicle obstruction	14
4.2.3.5	Glare from street lighting	14
4.2.4	General considerations	14
4.2.5	Highway lighting levels	15
4.2.6	Communication to site	15
4.2.6.1	Communication local link	15
4.2.7	Electrical connection	16
4.3	Camera selection criteria	16
4.4	Installation	17
4.4.1	Freestanding pole	17
4.4.2	Mounting brackets or mast arms	18
4.4.3	Roadside cabinets	18
4.4.4	Site acceptance testing	18
4.4.5	User acceptance testing	19
4.5	Vehicle-mounted cameras	19
4.6	Site assessment	19

4.7	Site audit.....	19
5	DESIGN FOR SAFETY.....	20
5.1	Health and safety	20
5.1.1	Health and safety in design	20
5.2	Safety outcomes.....	20
5.2.1	Space to ensure safety conformance.....	20
5.2.1.1	Hinge folding pole consideration.....	20
5.2.2	Site access	20
5.2.3	Parking	21
5.2.4	Safety issues – above and below ground	21
5.2.5	Electrical safety	21
5.2.6	Surge/lightning protection.....	21
5.3	Site assessment	22
5.4	Site audit.....	22
5.5	System-specific safety requirements	22
6	DESIGN FOR MAINTAINABILITY	23
6.1	Maintenance outcomes	23
6.1.1	Extreme weather or other environmental conditions.....	23
6.1.2	Asset labels	23
6.1.3	As-built documentation.....	23
6.1.4	Camera pole inspection and maintenance.....	23
6.1.4.1	Inspection.....	23
6.1.4.2	Maintenance.....	24
7	DESIGN FOR SECURITY.....	25
7.1	Security outcomes.....	25
7.1.1	Camera security	25
7.1.1.1	WiFi and Bluetooth.....	25
7.1.1.2	Passwords.....	25
7.1.2	Pole security	25
7.1.3	Vendor labels.....	25
7.2	Camera configuration	25
7.2.1	Firmware/software update.....	25
7.2.2	Factory default reset.....	26
7.2.3	HTTPS, TLSv1.2 and SSH protocols	26
7.2.4	SNMP	26
7.2.5	NTP	26
7.2.6	Multicast	26
7.2.7	Discovery broadcast protocols	26
7.2.8	Camera phone home.....	26
7.2.9	Logs.....	26
7.2.10	Privacy zones	26
7.2.11	Vendor security hardening	27
7.2.12	Port security.....	27

8	REFERENCES.....	28
8.1	Industry standards.....	28
8.2	Waka Kotahi standards, specifications and resources	28
8.2.1	Standards and specifications	28
8.2.2	Resources	28
8.3	ITS standard drawings	28
8.4	Other resources.....	29
9	CONTENT TO BE REDIRECTED	30
10	FULL VERSION HISTORY.....	31

List of tables

<i>Table 1. Selection criteria for operational cameras.....</i>	<i>16</i>
<i>Table 2. Selection criteria for web cameras</i>	<i>17</i>

1 DOCUMENT CONTROL

1.1 Document information

Document number	ITS-STND-CCTV-202304
Previous document number/s (if applicable)	ITS-07-01
Document status	Approved by National Manager, Programme and Standards (NMPAS)
[IF RETIRED] New document details	N/A
Online ISBN	978-1-99-106831-6
Document availability	The controlled version of this document can be accessed from https://www.nzta.govt.nz/roads-and-rail/intelligent-transport-systems/standards-and-specifications/its-current-interim-and-legacy-standards-and-specifications/

1.2 Document owner

Role	Head of Technology Engineering
Organisation	Waka Kotahi

1.3 Document approvers

This table shows a record of the approvers for this document.

Approval date	Approver	Role	Organisation
9/03/2023	Endorsed by Technical Standards Committee	Technical Standards Committee	Waka Kotahi
23/03/2023	Recommended by Ratification Group to endorse this document	Ratification Group	Waka Kotahi
24/04/2023	Approved by NMPAS	Delegated approver	Waka Kotahi

1.4 Version history – major changes

Document version control is the process of tracking and managing different versions (or drafts) of a document to easily identify the current iteration of a file.

This table shows a record of all major (published) versions of this document (**for Waka Kotahi use only**). To record minor versions (author updates, amendments etc), go to section 10 Full version history.

Version	Date	Updated by	Role and organisation	Reason
0.10	18/10/2022	Gary Nates	Lead author, Beca Ltd	Draft version updated for industry consultation
1.0	22/05/2023	Anandita Pujara	Document Manager, Waka Kotahi	Ratified and approved version released

2 TERMINOLOGY USED IN THIS DOCUMENT

Term	Definition
DRAFT	The document is being written and cannot be used outside of Waka Kotahi.
FINAL DRAFT (Pending ratification)	The document has been finalised and is pending approval and ratification by Waka Kotahi. It can be used for procurement at this status.
APPROVED (or ratified)	The document is an official Waka Kotahi document. Waka Kotahi projects and other road controlling authorities connected to Waka Kotahi back-end systems must include this document in the contracts. The obligation to follow the requirements in this document would come from the inclusion of the S&S document in the contract.
RETIRED	The document is obsolete, and/or superseded.
ADSL	Asymmetric digital subscriber line
AS/NZS	Australian/New Zealand standard
CCTV	Closed-circuit television
CoO	Concept of operations
FAT	Factory acceptance testing
GSM	Global System for Mobile Communications
HTTPS	Hypertext Transfer Protocol Secure
ITS	Intelligent transport systems
kA	Kiloampere
m	Metre
mm ²	Square millimetres
PTZ	Pan-tilt-zoom [camera]
NMPAS	National Manager, Programme and Standards
NTP	Network Time Protocol
NZIECP	New Zealand Electrical Code of Practice
S&S	Standards and specifications
SAT	Site acceptance testing
SNMP	Simple Network Management Protocol
SSH	Secure Shell (protocol)
TOC	Transport operations centre
TTM	Temporary traffic management
UAT	User acceptance testing
µs	Microsecond
VDSL	Very high-speed digital subscriber line

3 OVERVIEW AND OUTCOMES

This section defines the operational outcomes for ITS with respect to the transport network.

3.1 Purpose

The purpose of this document is to specify the design requirements associated with the installation of closed-circuit television (CCTV) operational cameras and web cameras by Waka Kotahi. These cameras are intended to be connected to the Waka Kotahi operations environment and network. The target application of this document is SM031 and SM032 – State highway construction and maintenance contract proforma manuals.

Design assurance is delivered through a series of design standards. The standards ensure road network level operational outcomes and design for safety, security and maintainability are accounted for in solutions being delivered to Waka Kotahi. Design standards address risks typically generated at the front end of traffic corridors or infrastructure projects. Their objective is to ensure solutions:

- i. address the correct operational need
- ii. are fit for purpose.

3.2 Overview

3.2.1 Definition

Waka Kotahi uses CCTV cameras for two main purposes.

- i. **Operational cameras** provide transport operations centres (TOCs) with operational visibility of key assets.
- ii. **Web cameras** provide the public with the ability to check traffic conditions from various websites.

The type of camera used depends on the functionality requirements:

- i. Pan-tilt-zoom (PTZ) cameras are large, high-quality, high-performance cameras for use on urban and high-volume traffic corridor environments. PTZ cameras also have wipers to clear condensation or rain from the lens housing.
- ii. Dome cameras are smaller, cost-effective cameras suited to areas where a full PTZ camera is not required. Dome cameras can be fixed or have PTZ functionality.
- iii. Fixed cameras are high-quality cameras but without PTZ ability.

For other forms of cameras such as incident detection cameras or automatic number plate recognition cameras, refer to the Waka Kotahi ITS S&S website.

3.2.2 Waka Kotahi ITS class

[Class definitions](#)

006 Cameras. Equipment used to view and capture footage of activity on the transport network.

3.3 Scope

This design standard sets out the requirements for the location selection, installation and commissioning of a CCTV camera. The intent is to describe the considerations that the designer must address when designing these assets.

The two types of CCTV cameras described in this document are:

- i. operational cameras
- ii. web cameras.

This design standard does not cover thermal cameras, infra-red cameras or any other forms of cameras.

Each new camera field installation shall typically consist of:

- i. camera, including lens and accessories
- ii. housing, including pan-tilt mechanism (included with the camera)
- iii. communications interface equipment
- iv. power supply
- v. CCTV pole (hinged or lowering pole) including pole foundation, or bracket (as required)
- vi. flange to connect CCTV to pole/bracket/mast arm
- vii. roadside cabinet, plinth and apron
- viii. paved access area
- ix. guardrail protection
- x. other accessories, as necessary.

The above list is not intended to be exhaustive and only provides high-level guidance to the designer. Requirements will vary from project to project, and a wider understanding of the project must be understood.

For procurement of operational cameras, refer to the latest version of ITS delivery specification: Closed-circuit television – operational cameras.

For procurement of web cameras, refer to the latest version of ITS delivery specification: Closed-circuit television – web cameras.

3.4 Outcomes

The outcomes of the project will be described in the concept of operations (CoO). Before design can be carried out, an understanding of why the asset is needed must be understood by the designer. This outcome requirement will change from project to project and therefore cannot be described in this design standard.

This design standard seeks to define best practice on the approach to design. The consideration of how the design meets the CoO is an important component of the design process.

Typical outcomes for operational CCTV cameras are to:

- i. enable TOCs to have operational visibility of the road network and key assets
- ii. enable decision support regarding network conditions
- iii. provide first-level assessment before response arrives on-site

- iv. enable situational awareness of the transport network
- v. enable network performance analysis
- vi. enable network safety analysis.

Typical outcomes for web cameras are for the public to view static images of the traffic conditions to make decisions about their journey, at a resolution that will not allow the public to identify individual people or vehicles.

3.4.1 Operational

The intended operational outcomes of this design standard are to:

- i. ensure the equipment is accessible for use (the reliability of the equipment will ensure that it is out of service for maintenance for very short periods)
- ii. provide the ability to view images in varying conditions that are of a high enough quality for situational awareness
- iii. ensure the camera is available and operational when required
- iv. ensure the camera is compatible with the operations systems used by the TOCs.

3.4.2 For users of the transport network

Web cameras allow transport network users to make informed journey choices.

3.4.3 For road controlling authorities and transport operations centres

Operational cameras provide TOCs with operational awareness of the transport network, allowing management of safety, incident response and demand.

4 DESIGN FOR OPERATION

This section defines the functionality required to achieve successful operation of the ITS.

Design must be carried out in the context of the operational outcomes of the specific project. Careful consideration should be given to the following.

4.1 Operational visibility

See the latest version of ITS core requirements guideline: Requirements for intelligent transport systems.

In the above core requirements guideline, operational visibility requirements are defined by road classification. This operational visibility should be incorporated within the CoO (refer to section 3.4 Outcomes of this design standard).

The level of camera visibility typically depends on the strategic importance of the road or whether an area is high-risk for incidents or congestion, eg the visibility within a high-volume tunnel might be 200% (at least two angles of all sections of the carriageway).

Where cameras are being installed on road corridors or shared use paths, the designer should consider the operational visibility of the corridor or path in its entirety. Consider mapping the location of any current cameras prior to embarking on choosing the location of any new cameras. This should include the current camera operating angles and operational sight lines, to identify where coverage is lacking or needing enhancement.

Some major assets such as tunnels may have additional operational visibility requirements. This may be over and above the requirements of the road classification that the asset is located within.

4.2 Site selection

The following sections list the design elements that must be met and considered when selecting individual camera locations. The site selection for the camera infrastructure must be able to meet the outcomes identified by the project and in the context of the CoO.

Assessment of the location of the camera must be carried out to verify the suitability of the location with regard to visibility achievable. This should be carried out by identifying lines of sight, typically using 3D modelling.

The TOC must be given an opportunity to agree to the final camera locations.

4.2.1 End-user requirements

The designer shall consider the following end-user requirements when choosing a camera location:

- i. What is the purpose of a camera? The standard pole height is 15m to the flange plate on the top of the pole, but this may be excessive if the objective is to see under a structure or if there are tall trees at an

intersection. Consider if a shorter pole or attaching the camera to an existing structure provides the required views.

- ii. What is it that the user needs to see? The chosen location will ideally maximise what can be seen with a single camera (known as design sight lines). It is good practice to maximise the usability of the camera by positioning it in a location where it can be used to observe all approaches to an intersection or interchange, rather than just up and down the main highway.
- iii. Is the camera too close to the viewed object so that it cannot all fit into a single view? For example, a camera placed on the corner of a large intersection may be too close if the whole intersection itself (aside from the approaches) is required to be viewed.

4.2.2 Privacy

Privacy of the public must be considered by the designer in the context of the CoO. The designer has two mechanisms that should be implemented:

- i. site selection, to maximise the view required by the CoO and minimise the unintended exposure of the public and the surroundings
- ii. privacy zones, a software add-on that must be configured for all cameras (see section 7.2.10 Privacy zones).

4.2.3 Environmental

The designer shall consider the topography of the traffic environment, as well as other environmental features that may impact viewing for end users. This should include the implications of climate change with special considerations to resilience, such as potential future inundation or increased natural hazards.

Visibility shadows (commonly known as blind spots) occur where an object obscures part of the view of the camera. These should be considered when selecting the optimal location of the camera. Where possible, visibility shadows should be minimised.

The designer may consider including extra cameras where a single camera does not provide the full required coverage for the location.

The closer the camera site is to a visibility shadow, the greater its impact on the field of view.

4.2.3.1 Infrastructure geometry

Cameras should be located on a crest where possible. This should maximise the coverage and minimise the visibility shadow caused by a change in gradient.

Cameras should be located on the outside of a curve where possible. This should maximise the coverage and minimise the visibility shadow caused by a change in the horizontal alignment.

For PTZ and dome cameras, placing them on the outside of the curve will also increase the angle of view and minimise the amount of panning required by the operator.

4.2.3.2 Trees and foliage

Trees and foliage are a common visibility shadow. Consider both the present state of trees and how the trees are likely to grow in the future. If areas are going to be planted, these may provide unwanted visibility shadows in the future.

4.2.3.3 Physical structures

There are many physical structures that provide visibility shadows. Common examples include:

- i. buildings
- ii. gantries
- iii. signs
- iv. pylons
- v. tunnel entrances and exits
- vi. bridge structures
- vii. embankments.

Lighting poles only provide visibility shadows when placed very near a camera.

Consider the cumulative impact of multiple structures within the camera view.

4.2.3.4 Vehicle obstruction

Cameras that are located too low to the ground may have their field of view blocked by larger vehicles. This may include over-height vehicles.

Cameras must be located at a height to avoid the glare from headlights.

4.2.3.5 Glare from street lighting

Obstructional glare from street lights needs to be taken into account when designing camera locations.

4.2.4 General considerations

- i. Ground conditions – this affects both the foundation design as well as the working environment for technicians when maintaining cameras. Avoid locations that are prone to flooding.
- ii. Underground services (for freestanding poles) – this affects fine-tuning of the position, the foundation design, and the method of construction.
- iii. Wind loading – poles can whip or shimmy in windy weather, which makes the image unwatchable and can affect the integrity of the camera and its mountings. The pole design, which in turn affects the foundations, must minimise vibration as much as possible. This can mean the use of a large-diameter pole or a pole with thicker wall construction. Sway is rarely a problem when viewed through the camera.
- iv. Is there a local restriction on the maximum height of a camera pole? One way to gain height is to put the pole on the approach embankment to bridges over the alignment of a motorway or expressway, or at the top of a cutting slope.
- v. The cost of providing communications and power to the camera should not be a driver in positioning it, except in the most extreme circumstances.
- vi. The cabinet must be safely maintained without hazard to the cabinet, maintenance personnel or public. The cabinet and maintenance activities must not block intervisibility between all types of road user.

4.2.5 Highway lighting levels

Highway lighting has generally been designed to AS/NZS 1158.1.1:2022 *Lighting for roads and public spaces – Part 1.1: Vehicular traffic (Category V) lighting – Performance and design requirements*.

Where lighting exists, the designer shall assume that the lighting level is as per the minimum allowed.

Where no lighting exists or is proposed, the designer shall not assume that it will be provided. Thermal cameras may be considered for these locations.

4.2.6 Communication to site

A communications link is required to connect the camera to the Waka Kotahi national control system. This link directly impacts the quality of the video image for the end user, and it is important to understand the bandwidth and latency at a site.

All communications to site should run through a roadside cabinet, as detailed in the latest version of ITS delivery specification: Roadside cabinets.

Where existing Waka Kotahi communications networks exist, use this backbone infrastructure in the first instance.

Projects must use the ITS communications network vendor contracted by Waka Kotahi and must follow approved Waka Kotahi network architecture.

Alternatively, there are a range of other communications options that can be utilised, including:

- i. leased lines from commercial providers (eg very high-speed digital subscriber line (VDSL), asymmetric digital subscriber line (ADSL) or fibre)
- ii. mobile communications, such as the Global System for Mobile Communications (GSM) (though this is the least-preferred option)
- iii. other communication options (such as satellite) that meet the bandwidth and latency requirements.

If cameras are to be deployed outside of a secure Waka Kotahi network, then security requirements must be discussed with a Waka Kotahi representative.

Where bandwidth is constrained, TOCs should be engaged to determine an appropriate method of communication or consideration for scaling down resolution or frame rate.

4.2.6.1 Communication local link

The designer must provide a communication local link from the camera to the roadside cabinet that is fit for purpose. Consideration should be given to the load capacity of any cables, including any cabling length restrictions.

Physical cabling should be prioritised over wireless options as it is a more reliable communication link and less susceptible to security breaches.

A camera's WiFi or Bluetooth must not be used in the communication local link.

4.2.7 Electrical connection

Power supplies must be sized for the appropriate level and purpose of the camera.

Operational cameras need to be sized for supply of power for 24 hours a day.

All power connections will terminate into the local roadside communications cabinet power distribution unit in order to provide local power isolation, as detailed in the latest version of ITS delivery specification: Roadside cabinets.

4.3 Camera selection criteria

Cameras should be selected to achieve the appropriate CoO, operational visibility and required design sight lines.

PTZ cameras must be considered for open environments where long views are required or where vehicles may need to be tracked over a long distance. PTZ should be selected where camera movement and zoom are the primary function of the camera.

Dome cameras must be considered for local views (eg intersections or local roads) and locations where vehicles need to be tracked over a short-to-medium distance.

Fixed cameras provide similar performance to PTZ cameras, without the ability to pan, tilt or zoom. These should be considered for locations where camera movement is not required or movement needs to be prevented for constant surveillance.

Fixed cameras may be installed together with PTZ and dome cameras to prevent operation contention. This provides the flexibility of a constant view of the traffic environment with the flexibility of tracking and focusing on areas of interest on the carriageway/road corridors for operational purposes.

Selection criteria for operational cameras can be found in Table 1, and selection criteria for web cameras can be found in Table 2.

Criterion	Camera type		
	PTZ	Dome	Fixed
Motorway and expressway (including ramps)	✓		✓
Urban road environments including intersections (non-motorway and expressway)	✓	✓	✓
Rural road environments (medium or long views required)	✓	✓	✓
Shared-use paths		✓	✓
Fixed view to prevent movement (eg viewing under a bridge)			✓

Table 1. Selection criteria for operational cameras

Criterion	Camera type		
	PTZ	Dome	Fixed
Motorway and expressway (including ramps)		✓	✓
Urban road environments including intersections (non-motorway and expressway)		✓	✓
Rural road environments		✓	✓
Shared-use paths		✓	✓

Table 2. Selection criteria for web cameras

4.4 Installation

Cameras may be installed either on a dedicated freestanding pole or mounted onto an existing structure.

The placement of the poles, bracket or mast arms must not obscure the view for road users of current infrastructure or street furniture, including signs.

With all methods of installation, cameras must be mounted to avoid vibration and sway. Poles can whip or shimmy in windy weather, which makes the image unwatchable and can affect the integrity of the camera and its mountings.

If a camera is located at the highest point on a structure, then the camera must be installed with a lightning rod and be earthed appropriately. The lightning rod and its cables should be positioned to prevent obscuring the desired viewing angles at all levels of zoom of the camera.

4.4.1 Freestanding pole

Cameras may be installed on one of the following three types of poles:

- i. hinge folding pole
- ii. wind-down pole
- iii. rigid pole (not preferred).

Rigid poles require the use of additional plant to raise technicians to the operating height of the camera (such as a cherry picker). This exposes technicians to a working-at-height risk, which could be prevented by selecting a different type of pole. This also increases the time needed for fault and maintenance activities, leading to cameras being available for less time operationally.

On hinge poles, the camera(s) and the counterweight need to be balanced appropriately.

All poles must provide a flange on which a camera can be installed.

Where poles are used, cables must run within the pole. Cables should be encased within a catenary wire (to avoid the cables being self-supporting).

For details on the pole requirements and considerations, see the latest version of ITS design standard: Civil and structural requirements.

4.4.2 Mounting brackets or mast arms

Cameras may be installed onto existing structures with the use of a mounting bracket or mast arms. These structures may include:

- i. gantries
- ii. retaining walls
- iii. traffic signal poles.

Where possible, brackets and mast arms should allow cameras to be brought to a safe, accessible level to allow technicians access for installation and maintenance.

4.4.3 Roadside cabinets

All cameras must be connected to a roadside cabinet. This will provide both communication links and power to the camera and pole (if required).

If a roadside cabinet is present near the camera location, consider connecting to the existing cabinet (if capacity allows).

Consider positioning the camera so it can view its own cabinet, if possible.

See the latest version of ITS delivery specification: Roadside cabinets.

4.4.4 Site acceptance testing

Site acceptance testing (SAT) shall be undertaken as required following installation and prior to commissioning. This SAT may include, but is not limited to:

- i. any repeat factory acceptance testing (FAT) as deemed appropriate
- ii. testing of the:
 - power supply
 - communications link(s)
 - camera image and functions, including movement and zoom (where required)
 - presets
 - privacy masks
 - wipers (where required)
- iii. identifying known visibility shadows or limits to the camera view
- iv. inspection of the site.

SAT must also include camera configuration, and this must be submitted to the Waka Kotahi Security Team.

4.4.5 User acceptance testing

Prior to commissioning, the contractor is required to have user acceptance testing (UAT) completed and approved. This is usually undertaken by the TOC directly from the operations centre (given the TOC is the end user for operational cameras and contact for web cameras).

This UAT may include, but is not limited to:

- i. testing:
 - latency
 - bandwidth
 - camera image and quality
 - camera functionality, including presets and switching between automatic and manual functions
 - full camera movement and zoom (if available)
 - response times when actioning the camera
 - during day time and night time
- ii. confirming known visibility shadows or limits to the camera view.

4.5 Vehicle-mounted cameras

Operational cameras may be mounted on top of vehicles. These cameras are intended to function while the vehicle is stationary and used during situational responses to supplement the footage for the TOC.

This is not accepted as a design solution for operational visibility or part of the CoO.

The mounting should be secured to prevent the camera from changing position while the vehicle is moving and from being removed easily or stolen.

Vehicles will be required to provide cameras with their own power source and an appropriate communication method to allow the camera to be operated remotely.

4.6 Site assessment

Site assessments must be undertaken to consider:

- i. required field of view and camera coverage area
- ii. availability of required power and communication links to the site.

4.7 Site audit

A site audit must be undertaken to affirm the intent of the CoO.

Consideration should be given to any scheduled or existing planting.

5 DESIGN FOR SAFETY

This section defines the requirements to ensure the ITS can be operated and serviced safely.

5.1 Health and safety

All ITS equipment must be designed to ensure installation and maintenance in accordance with the Health and Safety at Work Act 2015, and the designer is to use a Safe System approach.

5.1.1 Health and safety in design

Health and safety in design must be undertaken to identify any hazards and the appropriate interventions.

See the latest version of the Waka Kotahi *Health and safety in design minimum standard* (ZH/MS/01).

5.2 Safety outcomes

5.2.1 Space to ensure safety conformance

Health and safety in design must be undertaken to determine the appropriate space required to operate safely within the CCTV camera site. The space must accommodate the CCTV pole, a cabinet, and safety interventions (such as barrier protection if required), and it must allow further distance to the edge of the live lane depending on the speed environment.

A site safety assessment must be undertaken to determine the appropriate safety interventions.

5.2.1.1 Hinge folding pole consideration

Additional space is required for hinge folding poles. Hinge folding poles shall be aligned and located to swing down parallel to, and clear of, any carriageway. It should also clear the site roadside control cabinet or any other obstructions.

A flat concrete pad should be installed where the camera folds down.

5.2.2 Site access

The site must allow reasonable vehicle access for installation, and for reactive and routine maintenance. The site shall be accessible, and the CCTV camera maintainable, without the need for temporary traffic management (TTM). The design should:

- i. allow safe access to the site for maintenance vehicles
- ii. minimise the exposure to hazards posed between maintenance vehicles and personnel, and traffic in the live lane(s)
- iii. facilitate effective traffic control for any maintenance work above the carriageway.

5.2.3 Parking

To provide a safe parking location, sufficient space for manoeuvring should be provided. For reversing vehicles, rubber wheel stops should be installed where there is a risk of a vehicle hitting a pole, cabinet or other assets.

5.2.4 Safety issues – above and below ground

For safe distances from low- and high-voltage power lines, refer to the latest version of the NZECP 34:2001 *New Zealand Electrical Code of Practice for Electrical Safe Distances*.

The camera should not be located directly under or above any power lines.

Note that a check must also be made, using a Scala penetrometer, for the presence of underground services before digging or testing.

5.2.5 Electrical safety

All ITS equipment must comply with and be installed in accordance with Electricity (Safety) Regulations 2010 (SR 2010/36).

5.2.6 Surge/lightning protection

Where a camera is located at the highest point on a structure, the contractor must provide a surge/lightning protection system in accordance with AS/NZS 1768:2007 *Lightning protection*.

The surge/lightning protection system shall consist of:

- i. an air termination to intercept lightning discharges directly
- ii. down conductors to connect the air terminal to earth terminals (note that it is possible that these down conductors can be formed from reinforcing steel that is used to support concrete structures, as applicable)
- iii. earth terminations to discharge the lightning currents into the general mass of earth (note that this may in part, or in full, consist of the foundations for the support structure, depending on the calculated required maximum earthing resistance)
- iv. equipotential bonding between the lightning earthing system and any other earthing systems for personal and equipment protection
- v. provision of point-of-entry protection at the distribution board in each control cabinet and protection to at least 45kA (8/20µs or 10/350µs) (minimum 10mm² green copper conductors shall be used for the connections, and leads shall be as short as possible to prevent inductive voltage differentials).

Multi-stage surge diversion shall also be provided on the incoming power circuits and communication circuits.

Surge diverters shall be field replaceable without the need to disconnect wiring, and they must have integral indicators to show when they have blown.

5.3 Site assessment

A site assessment must be undertaken to consider:

- i. safe maintenance access to the site (without the need for TTM) and safe maintenance access within the site
- ii. site safety regarding passing traffic.

5.4 Site audit

A site audit must be undertaken to ensure the site is both safe to operate and safe to maintain.

5.5 System-specific safety requirements

Before any work is undertaken, cameras must be isolated from power appropriately.

6 DESIGN FOR MAINTAINABILITY

This section defines the requirements to ensure the ITS can be maintained.

6.1 Maintenance outcomes

6.1.1 Extreme weather or other environmental conditions

Avoid sites prone to flooding where possible. Consideration must be given to extreme or unusual conditions at each site that will require upgrading as part of the design.

Obvious examples include:

- i. extreme winds that are more likely at >500m altitude, on a ridge or cutting, or in a lee effect multiplier zone, affecting foundations and pole design
- ii. corrosive environments requiring enhanced coating systems, such as near coastlines.

Other less obvious examples include:

- i. alpine locations, where exposed equipment needs to be protected from wildlife
- ii. under or near trees, where cameras may attract spiders, ants, birds etc.

These should be integrated as part of section 5.1.1 Health and safety in design.

6.1.2 Asset labels

All assets are to be labelled to the satisfaction of the local Waka Kotahi Asset Manager.

6.1.3 As-built documentation

As-built drawings shall be supplied by camera vendors and contractors and will include (as required):

- i. site layout drawing and schematic
- ii. GPS coordinates of site
- iii. pole structure
- iv. installation elevations/plans
- v. cabinet drawings and schematic
- vi. power supply arrangements
- vii. electrical compliance certificates
- viii. camera make, model, firmware version and date installed.

6.1.4 Camera pole inspection and maintenance

6.1.4.1 Inspection

Inspection of camera poles or brackets/mast arms shall be undertaken in accordance with Waka Kotahi policies, specifications and guidelines, including any manufacturer recommendations. This should include inspections of any earthing rods.

6.1.4.2 Maintenance

Maintenance shall be undertaken where necessary at scheduled inspections.

Reactive maintenance shall be undertaken following the identification of defects, in accordance with Waka Kotahi requirements.

7 DESIGN FOR SECURITY

This section defines the requirements to ensure the ITS can be secured and maintain integrity.

7.1 Security outcomes

7.1.1 Camera security

7.1.1.1 WiFi and Bluetooth

WiFi and Bluetooth capability must be disabled.

7.1.1.2 Passwords

All passwords must be changed from their default.

Passwords must be at least 12 characters long and include lower case, upper case, numbers and special characters.

Passwords must not include any wording related to the device or usernames.

7.1.2 Pole security

All poles with an inspection hatch should be locked by either a key or a padlock with a key. Padlocks with an inbuilt combination lock are not permitted.

Hinge poles should be closed with both a bolt and a separate padlock with a key.

Consider a padlock bolt hole to prevent bolt cutters from being used to remove padlocks.

7.1.3 Vendor labels

Any vendor labels or labels identifying the camera on its exterior (such as the camera brand, manufacturer, name or type) must be removed or covered up.

7.2 Camera configuration

This section details how the camera should be configured securely when being installed.

Enable settings only after considering the CoO for the camera. This may include security protocols used for connectivity, management, monitoring, backup or data transfer.

7.2.1 Firmware/software update

The latest version of firmware and software must be installed on cameras.

7.2.2 Factory default reset

Prior to configuring a camera, a factory default reset must be undertaken in the first instance.

7.2.3 HTTPS, TLSv1.2 and SSH protocols

Configure and use Hypertext Transfer Protocol Secure (HTTPS), Transport Layer Security (TLSv1.2) and Secure Shell (SSH) protocol. Disable insecure protocols such as HTTP or Telnet.

7.2.4 SNMP

If Simple Network Management Protocol (SNMP) is used, then enable version SNMPv3.

Default SNMP settings must be disabled and default community strings deleted and not used (both public and private strings).

7.2.5 NTP

Cameras should be configured to use three Network Time Protocol (NTP) servers for time synchronisation.

7.2.6 Multicast

All multicast features must be disabled.

7.2.7 Discovery broadcast protocols

Disable discovery broadcast protocols, such as plug and play.

7.2.8 Camera phone home

Disable camera phone home functionality, such as cloud connect, management and automatic updates.

7.2.9 Logs

Cameras must have logging enabled for each instance when the camera is accessed for operations, monitoring, configuration/setting updates or to record faults.

Logs must be stored for at least 3 months on the camera.

7.2.10 Privacy zones

Privacy zones must be configured for all cameras, where identified by the site survey.

Operational cameras may require clearly viewing the carriageway/road shoulder and potentially land adjacent to the carriageway/road. This should be discussed with the TOC prior to configuring.

Web cameras should only view the traffic conditions, and all surrounding environments should be blurred or obscured by privacy zones.

7.2.11 Vendor security hardening

If a camera vendor has developed a security hardening guide, these measures should be considered and implemented where they do not conflict or contradict requirements in this design standard.

7.2.12 Port security

Cameras should be configured to communicate with the connecting device using port security (802.1x, MAC authentication) in compliance with the switch/router security configuration.

8 REFERENCES

This section lists all external and Waka Kotahi references included in this document.

8.1 Industry standards

Standard number/name	Source	Licence type and conditions
AS/NZS 1158.1.1:2022 Lighting for roads and public spaces – Part 1.1: Vehicular traffic (Category V) lighting – Performance and design requirements	Standards NZ website	Available for purchase
AS/NZS 1768:2007 Lightning protection	Standards NZ website	Available for purchase
NZIECP 34:2001 New Zealand Electrical Code of Practice for Electrical Safe Distances	Transpower website	Publicly available

8.2 Waka Kotahi standards, specifications and resources

8.2.1 Standards and specifications

See the [Waka Kotahi website](#) for the latest versions of the ITS design standards, delivery specifications and core requirements listed below.

Document name
ITS core requirements guideline: Requirements for intelligent transport systems
ITS delivery specification: Closed-circuit television – operational cameras
ITS delivery specification: Closed-circuit television – web cameras
ITS delivery specification: Roadside cabinets
ITS design standard: Civil and structural requirements

8.2.2 Resources

Document name/code	Waka Kotahi website link
Health and safety in design minimum standard (ZH/MS/01)	https://www.nzta.govt.nz/assets/resources/contractor-health-and-safety-expectations/ZHMS-01-Health-and-safety-in-design-minimum-standard.pdf

8.3 ITS standard drawings

See the [Waka Kotahi website](#) for the latest versions of the ITS standard drawings listed below.

Drawing number

8.4 Other resources

Name	Website link
Electricity (Safety) Regulations 2010 (SR 2010/36)	https://www.legislation.govt.nz/regulation/public/2010/0036/latest/DLM2763501.html
Health and Safety at Work Act 2015	https://www.legislation.govt.nz/act/public/2015/0070/latest/DLM5976660.html

9 CONTENT TO BE REDIRECTED

This section records any circumstances where content from this document will be reclassified and moved into future documents. This table is then updated with a reference to the new location.

Section reference	Section name	Future document	Class
5.2.3	Parking	To be determined	TBA
4.4.1	Freestanding pole, the following sentence only: All poles must provide a flange on which a camera can be installed.	Civil and structural requirements design standard	010 Civil infrastructure
4.4.4	Site acceptance testing	SAT test cases	03
4.4.5	User acceptance testing	UAT test cases	03
4.2.5	Communication to site	Communication standard	TBC
7.1.2	Pole security	Security standard	TBC

10 FULL VERSION HISTORY

This table shows the full history of changes made to this document, both minor and major, in chronological order, since the document was first authored.

Minor versions are numbered 0.1, 0.2 etc until such point as the document is approved and published, then it becomes 1.0 (major version). Subsequent edited versions become 1.1, 1.2 etc, or if it's a major update 2.0, and so on.

Version	Date	Author / updated by	Role and organisation	Reason
0.1	05/01/2018	Kevan Fleckney	Design Engineer, Waka Kotahi	First draft prepared
0.2	26/06/2020	Final Word	Editorial services	Transferring the draft document to the latest ITS design standard template
0.3	09/11/2021	Gary Nates	Lead author, Beca Ltd	Draft for Waka Kotahi Expert Panel
0.4	07/12/2021	Final Word	Editorial services	Proofread latest version
0.5	16/03/2022	Gary Nates	Lead author, Beca Ltd	Draft response to Expert Panel workshop
0.6	05/04/2022	Final Word	Editorial services	Proofread latest version
0.7	12/04/2022	Gary Nates	Lead author, Beca Ltd	Response to Final Word comments
0.8	19/04/2022	Final Word	Editorial services	Further queries for author and ITS Working Group
0.9	06/05/2022	Gary Nates	Lead author, Beca Ltd	Response to Final Word comments
0.10	18/10/2022	Gary Nates	Lead author, Beca Ltd	Response to RCA and Security comments
0.11	10/02/2023	Gary Nates	Lead author, Beca Ltd	Response to industry briefing
0.12	15/02/2023	Matthew Bauer	Editor, Clear Edit NZ	Copyedit
0.13	17/02/2023	Gary Nates	Lead author, Beca Ltd	Response to editorial service
0.14	22/02/2023	Matthew Bauer	Editor, Clear Edit NZ	Proofread
0.15	9/03/2023	Anandita Pujara	Document Manager, Waka Kotahi	Updated as per Technical Standard Committee feedback and security team consultation
0.16	18/05/2023	Matthew Bauer	Editor, Clear Edit NZ	Proofread
1.0	22/05/2023	Anandita Pujara	Document Manager, Waka Kotahi	Released final approved version 1.0